



# Walshville Trail (CH 11) Improvement Project

Public Information Meeting - Tuesday August 6, 2024


Montgomery  
County  
Highway  
Department



**whks**

engineers + planners + land surveyors

# Project Location



- ▶ Montgomery County, IL
- ▶ Walshville, IL
- ▶ Walshville Trail (CH 11) between Broadway Street and Hamby Lane

# Existing Walshville Trail (CH 11)

- ▶ A major collector roadway that connects Mt. Olive to Taylor Springs / Hillsboro
- ▶ Existing alignment goes through the Village of Walshville
- ▶ Streets on existing alignment
  - ▶ Locust Street
  - ▶ Broadway Street
  - ▶ Church Street
  - ▶ 3<sup>rd</sup> Street
  - ▶ A Street
  - ▶ Hamby Lane
- ▶ 6 sharp horizontal curves
- ▶ 500 vehicles travel this road per day (Average Daily Traffic)
- ▶ 6% of the traffic is truck traffic

Taylor Springs / Hillsboro




Mt. Olive

# Why is the project needed?

- ▶ Existing pavement is deteriorated
  - ▶ Roadway is currently maintained by the Village of Walshville
  - ▶ Proposed roadway will be paid for and maintained by the County Highway Department
- ▶ Existing curves do not meet design policy criteria (i.e. curves are non-compliant)
- ▶ Non-compliant curves increase the chance of a crash



# Existing Curve Design Speeds



# Goals of the Project

**Improve**

Improve safety of the roadway

**Reduce**

Reduce the number of curves

**Correct**

Correct non-compliant curves by increasing the design speed of the curves

**Balance**

Balance the need for improvement with amount of Right-of-Way needed

# Curve Design Speeds Considered



50 MPH

Compliant for new construction  
Needs the most land (Right-of-Way)  
926 ft = minimum curve radius



40 MPH

Compliant for future maintenance  
533 ft = minimum curve radius



30 MPH

Non-compliant, but improvement from existing  
Needs the least land (Right-of-Way)  
250 ft = minimum curve radius

# Alternative Alignments Considered

## Alternative 1: Existing Alignment with Improved Curves



- ▶ Stay on existing alignment
- ▶ 30 MPH curve design speed
- ▶ Alternative Eliminated
  - ▶ Does not reduce the number of curves
  - ▶ Requires relocating 2 residential homes



# Alternative Alignments Considered


## Alternative 2: Realignment on Existing Roads



- ▶ Realign on Pearl Street
- ▶ 30 MPH curve design speed
- ▶ Alternative Eliminated
  - ▶ Does not reduce the number of curves
  - ▶ Requires improving the railroad crossing on Church Street

# Alternative Alignments Considered


## Alternative 3: New Road with 50 MPH Curves



- ▶ Realign to the south and east of Walshville
- ▶ 50 MPH curve design speed
- ▶ Alternative Considered
  - ▶ 4 curves
  - ▶ Compliant curves for new construction
  - ▶ No impacts to buildings
  - ▶ Approximately 7.5 acres of Right-of-Way
  - ▶ Tree removal needed
  - ▶ Utility relocation needed

# Alternative Alignments Considered


## Alternative 4: New Road with 40 MPH Curves



- ▶ Realign to the south and east of Walshville
- ▶ 40 MPH curve design speed
- ▶ Alternative Considered
  - ▶ 4 curves
  - ▶ Compliant curves for maintenance
  - ▶ No impacts to buildings
  - ▶ Approximately 4.7 acres of Right-of-Way
  - ▶ Tree removal needed
  - ▶ Utility relocation needed

# Alternative Alignments Considered


## Alternative 4A: New Road with 40 MPH Curves - Tangent



- ▶ Realign to the south and east of Walshville
- ▶ 40 MPH curve design speed
- ▶ Alternative Considered
  - ▶ 2 curves
  - ▶ Compliant curves for maintenance
  - ▶ No impacts to buildings
  - ▶ Approximately 4.7 acres of Right-of-Way
  - ▶ Tree removal needed
  - ▶ Utility relocation needed

# Alternative Alignments Considered

## Alternative 5: New Road with 30 MPH Curves



- ▶ Realign to the south and east of Walshville
- ▶ 30 MPH curve design speed
- ▶ Alternative Considered
  - ▶ 4 curves
  - ▶ Non-compliant curves for maintenance
  - ▶ No impacts to buildings
  - ▶ Approximately 4.3 acres of Right-of-Way
  - ▶ Tree removal needed
  - ▶ Utility relocation needed

# Alternative Alignments Considered

## Comparison of Feasible Alternatives

### Alt 3

- \$2,364,500 estimated cost
- 7.5 acres estimated ROW needed
- Safest option

### Alt 4

- \$2,167,000 estimated cost
- 4.7 acres estimated ROW needed
- Safer than existing

### Alt 4A


- \$2,168,500 estimated cost
- 4.7 acres estimated ROW needed
- Safer than existing

### Alt 5

- \$2,001,500 estimated cost
- 4.3 acres estimated ROW needed
- Slightly safer than existing

# Recommended Alignment

## Alternative 4A: New Road with 40 MPH Curves - Tangent



- ▶ 40 MPH curve design speed
- ▶ 2 curves
- ▶ Compliant curves for maintenance
- ▶ No impacts to buildings
- ▶ Approximately 4.7 acres of Right-of-Way
- ▶ Tree removal needed
- ▶ Utility relocation needed
- ▶ \$2,168,500 estimated cost

# Recommended Alignment

## Alternative 4A: New Road with 40 MPH Curves

Why Alt 4A (40 MPH) instead of Alt 3 (50 MPH)?

Less cost

Less Right-of-Way impacts

Why Alt 4A (40 MPH) instead of Alt 5 (30 MPH)?

Similar Cost

Similar Right-of-Way impacts

Alt 4A is safer due to higher design speed for curves

Why Alt 4A (40 MPH - Tangent) instead of Alt 4 (40 MPH)?

Similar Cost


Similar Right-of-Way impacts

Alt 4A is safer due to less curves



# Recommended Alignment

## Alternative 4A: New Road with 40 MPH Curves




# Land Acquisition Process (Right-of-Way)

What if the project goes through my property?

- ▶ Land purchased for this project will comply with The Uniform Act
- ▶ Overview of the Land Acquisition Process



We Are Here



### Phase I Design

### Land Acquisition

### Phase II Design

### Construction

### Roadway Opens

Preliminary Design Reports

Negotiate Right-of-Way Purchases

Prepare the Plans  
Estimated Completion  
Summer 2026

Build the Project  
Estimated Start Fall  
2027

Estimated Completion  
Winter 2027

Estimated Completion  
Summer 2025

Estimated Completion  
Summer 2026

# Anticipated Project Schedule

# Questions / Concerns?

- ▶ Exhibits from this presentation are on display around the room.
- ▶ Team members are here to discuss the project with you.
- ▶ Comment forms are provided for you to submit written comments, questions, and concerns to be considered in the design process for the project.
- ▶ Thank you for watching. Presentation will begin again shortly.

